

QUOTATION

S/N	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
CIVIL WORK					
1	Dismantling Work: All kind of of dismantle work & remove all rubbish from site.	job	1		
2	Brick Wall: <u>New Toilet & required area as per design</u> Fabrication, Supply and installation / fitting-fixing of 5" brick wall as per design; all complete as per design-drawing and instruction of Architect/Engineer-in-Charge.	job	1		
3	Plaster Work <u>New Toilet & required area as per design</u> Fabrication, Supply and installation / fitting-fixing of 15mm plaster work as per design; all complete as per design-drawing and instruction of Architect/Engineer-in-Charge.	job	1		
4	Tiles Work: <u>New Toilet (wall & Floor) & required area as per design</u> Fabrication, Supply and installation / fitting-fixing of 15mm plaster work as per design; all complete as per design-drawing and instruction of Architect/Engineer-in-Charge.	job	1		
5	Toilet PVC Door: Fabrication, Supply and installation / fitting-fixing of Toilet PVC door with door frame; all ancillary item required for work; all complete as per design-drawing, approved sample and instruction of Architect/Engineer-in-Charge.	nos	1		
6	Commode Set: Fabrication, Supply and installation / fitting-fixing of commode (Brand: RAK/Stella/Haibali); all ancillary item required for work; all complete as per design-drawing, approved sample and instruction of Architect/Engineer-in-Charge.	nos	1		
7	Basin Set: Fabrication, Supply and installation / fitting-fixing of commode (Brand: RAK/Stella/Haibali); all ancillary item required for work; all complete as per design-drawing, approved sample and instruction of Architect/Engineer-in-Charge.	nos	1		

8	Toilet High window : Fabrication, Supply and installation / fitting-fixing of toilet high window; all ancillary item required for work; all complete as per design-drawing, approved sample and instruction of Architect/Engineer-in-Charge.	job	1		
9	Plumbing works	job	1		-
SUB TOTAL (BDT) =					-
INTERIOR WORK					
1	Dry Wall Fabrication, Supply and installation / fitting-fixing of 3" Size Metal C & U Chanel For Framing & 12mm Plain woodtex board as Partition wall with Plastic Paint; All ancillary item as required for works; all complete as per drawing - design and instructions of Engineer-in-Charge.	sft	460		
2	Flush Door: Fabrication, Supply and installation / fitting-fixing of flush door with door frame & polish; all ancillary item required for work; all complete as per design-drawing, approved sample and instruction of Architect/Engineer-in-Charge.	nos	3		
3	PVC Ceiling Work for Toilet: Garjon wood Framing,2'X2' pvc board ceiling. Complete as per direction of the Engineer-in-Charge.	job	1		
4	Wall & Ceiling Plastic Paint Painting with synthetic plastic emulsion (Approved quality berger / asian paint) of approved color.	sft	9000		
5	Vertical Blinds	sft	301		
SUB TOTAL (BDT) =					-
FURNITURE WORK					
1	Service Counter Made of 16mm melamine board with pvc edging; all ancillary item required for work; all complete as per design-drawing, approved sample and instruction of Architect/Engineer-in-Charge.	nos	6		
2	Drawer Unit Made of 16mm melamine board with pvc edging; all ancillary item required for work; all complete as per design-drawing, approved sample and instruction of Architect/Engineer-in-Charge.	nos	6		
3	Round Table : Fabrication, Supply and installation / fitting-fixing of MS structure with f25mm melamine board top & pvc edging; all ancillary item required for work; all complete as per design-drawing, approved sample and instruction of Architect/Engineer-in-Charge.	nos	1		

4	3 Seater Waiting Chair Fabrication, Supply and installation / fitting-fixing of ss Waiting Chair; all ancillary item required for work; all complete as per design-drawing, approved sample and instruction of Architect/Engineer-in-Charge.	nos	7		
5	2 Seater Waiting Chair Fabrication, Supply and installation / fitting-fixing of ss Waiting Chair; all ancillary item required for work; all complete as per design-drawing, approved sample and instruction of Architect/Engineer-in-Charge.	nos	6		
7	Executive Chair : Supplying swivel chair of official standard size of zinc phosphate coated oven baked powder paint finish mild steel structure, chrome plated polymer cast leg with 5 nos. castors (wheels). High quality PVC handles, fully revolving and back tilt facility, hydraulically height adjustable mechanism. Foam cushioning seat and back pasted on imported seat & back covered by mesh fabric, all surface are black colour coat finish. Sample and colour should be approved by the authority.	nos	11		
8	Pantry Cabinet with Marble Top Made of 16mm melamine board with pvc edging; all ancillary item required for work; all complete as per design-drawing, approved sample and instruction of Architect/Engineer-in-Charge.	sft	21		
9	Dining Table : Fabrication, Supply and installation / fitting-fixing of MS structure with formica pasted table top & wooden edging; all ancillary item required for work; all complete as per design-drawing, approved sample and instruction of Architect/Engineer-in-Charge.	nos	1		
10	Dining Chair : Supplying swivel chair of official standard size of zinc phosphate coated oven baked powder paint finish mild steel structure. Foam cushioning seat and back pasted on plywood seat & back covered by rexin, all surface are black colour coat finish. Sample and colour should be approved by the authority.	nos	6		
11	Plantation Box : Made of 18mm garjon plywood with enamel paint; all ancillary item required for work; all complete as per design-drawing, approved sample and instruction of Architect/Engineer-in-Charge.	nos	2		
SUB TOTAL (BDT) =					-

ELECTRIC WORK					
1	Wiring / Cable Work Supply & laying of following size single core wire / cable in pre-installed pipe with accessories,				
	a) 1.5 RM S/C BYA	rft	3280		
	b) 1.5 RE S/C BYA	rft	1640		
	c) 2.5 RM S/C BYA	rft	1968		
2	Electric pope work, steel box, base plate, groove cutting work	L/S	1		
3	2/3/4 Gang Switch (MK)	nos	12		
4	6 Pin Multi Socket (MK)	nos	15		
5	Hanging Tube Light Set	nos	48		
6	12W LED Panel Lite	nos	12		
7	Installation of 32A (SP) Circuit breaker (MCB) for power with imported brand (Legrand)	nos	12		
8	Installation of 63A (TP) Circuit breaker (MCB) for power with imported brand (Legrand)	nos	1		
9	SDB Box Supply, Fitting & Fixing	nos	1		
				SUB TOTAL (BDT) =	-
				GRAND TOTAL =	-